Sonny's CarWash Equipment

Sonny's 110-EDT

Exterior Detail Hybrid Tunnel System

Wash, Wax, Seal, Tire Shine & Dry

Up To 125 Cars Per Hour!

Tunnel Equipment: $328,024 + Support Equipment: $141,980

$470,004



Over-Under Conveyor

- 110-foot Painted Rear Wheel Push
- Air Take-Up
- Hydraulic Drive
- Log Chain
- Direct-Connect Rollers
- 8ft x 25in Correlator
- Banana Peel Guide Rails
- Fiberglass Grating

Includes:

- ☑ All Required Support Equipment
- ☑ 15 RAINBOW MAXX™ LED LIGHTS
- ☑ FUSION PROCESS™
- ☑ CERAMIC X³ — **Ceramic X³** Raise your average ticket with a longer lasting deeper shine.

Optional:

Custom Color Powder Coating Option
Contact your Sonny's Sales Representative for details

Join Sonny's OneWash and Save

*Optional support equipment, installation and powder coating is not included in total price. Site plans are FREE with any Complete Tunnel System purchase. Site-specific mechanical drawings are also FREE after initial deposit and equipment package choices are finalized.

110-EDT Tunnel System Includes:

1



Entrance Arch & Pre-Soak Applicators

2 - Rainbow MAXX LED Lights

Mr. Foamer Fully Lit Pinnacle Arch. Dual CTA's. Dual Directional Bumper Applicator. Dual Directional Pre-Soak Arch with Foaminator MAXX for Fusion Bath Application with LED Lights

2



SFM901 Double Jog Spyder Wrap Combo

1 - Rainbow MAXX LED Light

SFM901 Spyder with MicroClean Mitter. Hydraulic Entrance & Exit Double Jog Wraps with NEOGLIDE Hush. Attached Hydraulic Poodle Plus Tire Brush with 21" NEOGLIDE Hush Rockers. Undercarriage Wash Manifold. Banana Hybrid Kit for Tri-Foam. Foaminator MAXX Stream with LED Light for Fusion Prime Application.

3



Omni 352 High-Pressure Wash

1 - Rainbow MAXX LED Light

Hydraulic Omni 352 Arch with Attached Octopus Mirror Blaster and Rinse Stream MAXX with LED Light for Fusion Rinse Application.

4



SFM 807 Pendulum Combo

4- Rainbow MAXX LED Lights

SFM807 Side to Side Mitter with MicroClean & Pendulum Spinners. Foaminator MAXX Streams with LED Lights for Fusion Seal or CeramicX3 Step One Applications. Foaminator MAXX Streams with LED Lights for Fusion Wax or CeramicX3 Step Two Applications.


5



RainMA Arch

10' Rain Multi Arch with 2 Manifolds – Rinse & Drying Agent and Attached Rain-Bar Mirror Rinse. Banana V-Jets for Fusion Rain Repel Application.

6



CeramicX3 Applicator Arch

3 - Rainbow MAXX LED Lights

Grand Arch with LED Lights and Foaming Rain bar for CeramicX3 Final Step. Attached Winged Rain manifold for Spot Free Rinse.

7



150 HP Drying System

4- Rainbow MAXX LED Lights

(4) Arches with (10) 15HP Producers including (1) Duck Bill and (2) Sets of Pivoting Mammoths. All blowers have Gator Gates for instant air control. (4) LED Lights for Toaster Effect.

8



Buff-N-Dry & Tire Seal Combo

Electric Buff-N-Dry with Wick-A-Way Hush Drying Material. Attached Hydraulic Tire Seal and Mammoth Dryers.

Included:

Support Equipment

Required Chemical Stations
3-Panel Chemical Concierge Dispensing System with VFD Booster Pump. 3 Single Foaming Dosatrons for CeramicX3 Application.

Required Pump Stations
(1)H-25 Dual and (1) H-25 Single High-Pressure Pumping Stations.

Required Hydraulic Power Packs
(1) Twin 7.5, (3) 7.5HP, (1) 5HP, and (1) 3HP Hydraulic Power Packs.

Required Air Compressors
(2) 10HP Vertical 120 Gallon Ingersoll Rand Compressor, and (1) Ingersoll Rand 64 CFM Air Dryer.

Required Control Systems
(1) Motor Control Center, (1) Photo Eye Entrance System, (2) Entrance Tape Switches, (1) Conveyor Pulse Kit.

COMPLETE YOUR SYSTEM



Pay Stations
Page 224



Vacuum Systems
Page 192



Signage
Page 244

© 2020 SONNY'S Enterprises, LLC. All prices & availability subject to change without notice.

SONNY'S The CarWash Factory